

298

**MAHANADI COALFIELDS LIMITED,  
JAGRITI VIHAR, BURLA, SAMBALPUR(ORISSA)**

REF: MCL/SAMB/Civil/DSR-2007/Circular/08-09/1388

Date 26.11.2008

**SUB: Circular regarding Analysis and rate of Brick work items of DSR-2007.**

As per the size (25x12x7.5 cms) and class of bricks (Class desg 50) locally available and being used in MCL, the following points are being circulated for adoption in estimating and analysis of Brick work items of DSR-2007:

1. Number of bricks to be considered for analysis of rate of Brick work items:
  - i. Full Brick Work (Unit Cum)- 385 nos. per cum of brick work.
  - ii. Half Brick Work (Unit Sqm)- 480 nos. per 10 sqm of brick work.
2. Deduction in rates of DSR-2007 brick work items for using class desg. 50 bricks in place of class desg. 75 bricks.
  - i. Full Brick Work (Unit Cum)- Rs. 114.75 per cum.
  - ii. Half Brick Work (Unit Sqm)- Rs. 13.10 per sqm.

*B. C. Mishra*  
26/11/08  
(D.C. Mishra),  
Chief General Manager(Civil)

Cc to:

1. CGM/GM, All the Areas of MCL.
2. CGM/GM(Finance), MCL HQ
3. SO(Civil), All the Areas of MCL
4. AFM, All the Areas of MCL.
5. AFM, HQ
6. Dy. C.E(Civil)-I/ Dy. C.E(Civil)-II/ Dy. C.E(Civil)-III, MCL HQ
7. Nodal officer, BBSR ✓
8. SE©, Updation/SE©, TC/ SE©, PDC, MCL HQ

For kind information:

1. Director(Personal), MCL
  2. Director(Finance), MCL
  3. Director(Technical), MCL
  4. Director(Technical), P&P, MCL
  5. Chief Vigilance Officer, MCL.
- Choudhary*